



LEGEND / NOTES.	
	EXISTING TACTILE PAVING UNITS
	PROPOSED TACTILE PAVING UNITS (450MM X 450MM) BUFF COLOUR
	GRANITE KERBS (150mm X 300mm) LAID FLUSH
	GRANITE KERBS (300mm X 300mm) LAID FLUSH
	TAPER GRANITE KERB (150mm X 300mm) LAID WITH A SLOPE OF 1:15
	GRANITE KERB (150mm X 300mm) LAID WITH 100-120 mm UPSTAND
	GRANITE KERB (300mm X 300mm) LAID WITH 100-120 mm UPSTAND
	GRANITE KERB (150mm X 300mm) LAID WITH 20-25mm UPSTAND FROM TABLE TOP
	GRANITE KERB (150 X 300mm) LAID FLUSH ACROSS TABLE TOPS AND RAMPS
	PROPOSED DOUBLE YELLOW CARRIAGEWAY LINING, 50mm
	PROPOSED YELLOW CARRIAGEWAY LINING, 50mm
	EXISTING CARRIAGEWAY LINING
	PROPOSED CARRIAGEWAY LINING
	REMOVE KERB AND TAKE TO STORE FOR REUSE
	ASPHALT NEW PAVEMENT
	40MM RESIN BOUND GOLDEN AGGREGATES
	3MM RESIN BONDED FOOTWAY GOLDEN SURFACING
	RAMP - 2M LONG - SMA 20MM
	FOOTWAY SMA 6mm 30mm SURFACING
	PROPOSED 200MM X 100MM ANDOVER BLOCK PAVING (80mm THICK)
	PRECAST INTERLOCKING BLOCKS (MIXED COLOUR MID GREY / PINK GRANITE)
	BLUE GRANITE SLABS (300mm by random) PAVING (65mm THICK) (MIXED COLOUR OF GRAY/BLUE)
	BLUE GRANITE SLABS (300mm by random) PAVING (80mm THICK) (MIXED COLOUR OF GRAY/BLUE)
	CEDEC SURFACE (silver grey) 1-3mm AGGREGATES
	TOP SOIL - COMPOSITION TO BE SPECIFIED
	PROPOSED 450MM X 450MM GULLY
	EXISTING GULLY TO BE RETAINED OR RAISED
	EXISTING GULLY TO BE REMOVED
	NEW LAMP COLUMN
	REMOVE LAMP COLUMN
	EXISTING LAMP COLUMN TO BE RETAINED
	NEW BOLLARD
	REMOVE BOLLARD
	EXISTING BOLLARD TO BE RETAINED
	NEW POST AND SIGN
	REMOVE POST AND SIGN
	EXISTING POST AND SIGN TO BE RETAINED
	DRAINAGE 150MM PIPE RUN
	PROPOSED / EXISTING DRAW PIT FOR LAMP COLUMN
	ELECTRIC DUCT
	TREE NEW
	TREE EXISTING
	BENCH NEW
	FEATURE ROCKERY
	FLOWERS & COLOURED PLANTS
	ORNAMENTAL GRASSES

© Crown copyright and database rights 2015 Ordnance Survey 100024328

Drawn By	NM
Drawing No.	LNCA-N7-001
Date	24/03/2020
Scale	1:500

Title

COPPERMILL_AREA

INFORMAL_CROSSING_1

DETAILED DESIGN

Notes

