



LEGEND / NOTES.

	EXISTING TACTILE PAVING UNITS		PROPOSED 450MM X 450MM GULLY
	PROPOSED TACTILE PAVING UNITS (450MM X 450MM) BUFF COLOUR		EXISTING GULLY TO BE RETAINED OR RAISED
	GRANITE KERBS (150mm X 300mm) LAID FLUSH		EXISTING GULLY TO BE REMOVED
	GRANITE KERBS (300mm X 300mm) LAID FLUSH		NEW LAMP COLUMN
	TAPER GRANITE KERB (150mm X 300mm) LAID WITH A SLOPE OF 1:15		REMOVE LAMP COLUMN
	GRANITE KERB (150mm X 300mm) LAID WITH 100-120 mm UPSTAND		EXISTING LAMP COLUMN TO BE RETAINED
	GRANITE KERB (300mm X 300mm) LAID WITH 100-120 mm UPSTAND		NEW BOLLARD
	GRANITE KERB (150mm X 300mm) LAID WITH 20-25mm UPSTAND FROM TABLE TOP		REMOVE BOLLARD
	GRANITE KERB (150 X 300mm) LAID FLUSH ACROSS TABLE TOPS AND RAMPS		EXISTING BOLLARD TO BE RETAINED
	PROPOSED DOUBLE YELLOW CARRIAGEWAY LINING. 50mm		NEW POST AND SIGN
	PROPOSED YELLOW CARRIAGEWAY LINING. 50mm		REMOVE POST AND SIGN
	EXISTING CARRIAGEWAY LINING		EXISTING POST AND SIGN TO BE RETAINED
	PROPOSED CARRIAGEWAY LINING		DRAINAGE 150MM PIPE RUN
	REMOVE KERB AND TAKE TO STORE FOR REUSE		PROPOSED / EXISTING DRAW PIT FOR LAMP COLUMN
	ASPHALT NEW PAVEMENT		ELECTRIC DUCT
	40MM RESIN BOUND GOLDEN AGGREGATES		TREE NEW
	3MM RESIN BONDDED FOOTWAY GOLDEN SURFACING		TREE EXISTING
	RAMP - 2M LONG - SMA 20MM		BENCH NEW
	FOOTWAY SMA 6mm 30mm SURFACING		FEATURE ROCKERY
	PROPOSED 200MM X 100MM ANDOVER BLOCK PAVING (80mm THICK)		FLOWERS & COLOURED PLANTS
	PRECAST INTERLOCKING BLOCKS (MIXED COLOUR MID GREY / PINK GRANITE)		ORNAMENTAL GRASSES
	BLUE GRANITE SLABS (300mm by random) PAVING (65mm THICK) (MIXED COLOUR OF GRAY/BLUE)		
	BLUE GRANITE SLABS (300mm by random) PAVING (80mm THICK) (MIXED COLOUR OF GRAY/BLUE)		
	CEDEC SURFACE (silver grey) 1-3mm AGGREGATES		
	TOP SOIL - COMPOSITION TO BE SPECIFIED		

© Crown copyright and database rights 2015 Ordnance Survey 100024328

Drawn By	NM
Drawing No.	LNCA-N7-001
Date	24/03/2020
Scale	1:500

Title

COPPERMILL_AREA

INFORMAL_CROSSING_2

DETAILED DESIGN

Notes

